

# ADDENDUM NO. 2

**DATE:** August 25, 2011  
**TO:** All Plan Holders  
**FROM:** Philip Humphrey  
**PROJECT:** **CFPUA: VACUUM LOADER STORAGE BUILDING**  
Wilmington, NC

**John  
Sawyer  
Architects**

JOHN R. SAWYER  
PHILIP G. HUMPHREY  
DOUGLAS K. SHERWOOD

- 
1. The pre-bid meeting date, place and time remain unchanged.
  2. The bid date, place and time remain unchanged.

## SPECIFICATION ITEMS

1. BID FORM: Bid opening date and time should read: August 31, 2011 at 3:00pm. Please change date accordingly.
2. CONTRACTOR'S QUALIFICATION STATEMENT: Please pay attention to Item 6: Subcontractors providing 20% or more of the total work shall complete a qualification statement which shall be turned in with the General Contractor's at time of bid.
3. Section 083323 – Overhead Coiling Doors, Part 1.2: Item B – Delete: "B. Seismic Performance."
4. Section 083323 – Overhead Coiling Doors, Part 2.7, Item C – is to read, "Curtain R-Value: 6.0 minimum".
5. Section 083323 – Overhead Coiling Doors, Part 2.7, Item J – Delete: "Powder-Coated Finish".
6. Section 133419 – Metal Building Systems, Part 2.6, Item B – Delete: "Match profile and".

## DRAWING ITEMS

1. None at this time.

## CLARIFICATIONS

1. Wall panels are to be three-coat fluoropolymer.
2. The interior liner panel is continuous around perimeter.
3. The required collateral load for the Metal Building System is 3psf.

**BIDDERS LIST**

A current bidders list may be obtained from our website:  
[www.johnsawyerarchitects.com](http://www.johnsawyerarchitects.com), click under "Current Projects", or by  
calling our office and providing a fax number.

**END OF ADDENDA TWO**